should also be prepared to adopt any change in the location of control points and other outlets that might be suggested by the undersigned during the progress of the work without extra cost if the tender is not materially affected by such deviations.

7. The undersigned reserves the right also to reject the work either in full or in part if he finds the work not carried out in terms of the specifications or in otherwise dissatisfied with the workmanship.

8. *Name of work.*—Installing Five Globe Lights on Ornamental Pillars at the Town Railway Station, Shimoga.

9. *Last date for receiving tenders.*—3rd July 1939.

10. *Date and time of opening the tenders in public.*—3rd July 1939 at 4 P.M.

11. A period of three weeks will be allowed for final completion of the work with effect from the date of final acceptance of the tender. A penalty of Rs. 5 (Rupees five) for each day's delay over and above the stipulated period during the first week and Rs. 10 (Rupees ten) during the 2nd week will be imposed. If there be further delay the Department will take charge of the installation at whatever stage it might be and arrange for its completion through any other agency entirely at the risk of the tenderer.

12. It will be obligatory on the part of the tenderer executing the work to attend to any major troubles that might crop up due to bad workmanship, etc., during the first twelve months from the date of handing over the installation to this department without any return for services rendered.

13. *Details of work.*—The quantities given in the annexed statement are not guaranteed and are subject to variation at the time of executing the work.

Details of work.

Sl. No.	Names of materials, etc.	Unit	Quantity
1	Supplying and running No. 8 B. & S. insulated wires of 2,500 meg. ohms. grade in ¾" W. I. pipe from the meter board to the cable junction box embeded in the wall with necessary bends, etc., with accessories ..	Ft.	10
2	Supplying and laying No. 8 B. & S. Twin Conductor, V. C. Insulated lead covered double steel, tape armoured, jute served underground cable in a trench 3' deep, surrounding the cable with 3" river sand, enclosing the one end of the cable with an indoor type C. I. Junction Box filled with bitumen, complete with accessories	,,	545
3	Supplying and fixing outdoor type C. I. Junction Box, 3-way suitable for twin case cable filled with bitumen, etc., complete	No.	1
4	Supplying and fixing and wiring Ornamental Lamps Post fluted type, complete with cement concrete foundation form No. 8, Novalux fixture, Mysore type Monax No. 39 Globe, complete with underground C. I. Junction Boxes filled with bitumen, using No. 14 B. & S., I. C. twin conductor cable for tops and controlled by a 5 amp. Bakelite switch with 5 amp. fuse cutout housed at the base of the lamp post complete with 300 Watts, 220 volts, S. B. lamps, (Globe fittings will be supplied departmentally)	,,	5

K. SUBBA RAO,
Superintendent.

MYSORE STATE RAILWAY.

OFFICE OF THE DISTRICT TRAFFIC SUPERINTENDENT, MYSORE.

Notification No. T. M. 49—39, dated 7th June 1939.

The public are hereby informed that the right of selling light refreshments, fruits, cigarettes only from 1st July 1939, on the platform of Bidadi Station will be sold by public auction by the Traffic Inspector, Mysore State Railway, Mysore at 11 hrs. on 23rd inst. at Bidadi Railway Station.

The period of contract is upto 30th June 1940.

The successful bidder will have to deposit the full amount of bid immediately the bid is accepted by the Traffic Inspector, with an additional sum of annas ten towards the cost of bond to be executed, failing which it will be re-auctioned at his risk. He should also furnish a list of refreshments to the Traffic Inspector with rates of selling.

The sale is subject to the confirmation of the Traffic Manager, Mysore State Railway, Mysore, whose decision is final. He is not bound to accept the highest or any bid and may reject any bid without assigning any reason.

MIR ENAYETH HUSSAIN,
District Traffic Superintendent.